



ADDENDUM #5

RFT No. 36521-90930-T01 Aberdeen Pavilion End Wall Repair

Date: May 26, 2021

The Following modifications and clarifications are to be made and taken into consideration for the above referenced RFT and shall become a part of any resulting contract.

Instructions:

1. All works, including scaffolding and shoring are to be contained to the interior of the building.
2. Lead paint on the concrete slab shall be removed as necessary to accommodate all temporary works.
3. Washroom structures on the east side of the Pavilion cannot be used for the support of temporary works unless reviewed and verified by the contractors engineer. Record construction documents for these existing structures are not available.
4. Survey referenced in "PROCEDURE FOR COLUMN STRAIGHTENING" to be completed by competent individual with experience in the building construction surveying and steel erection.

Clarifications:

Question and Answers:

Q1. During the straightening procedure of the existing steel columns which will be through mechanical force we are concern that breakage of the window glazing may occur , also malfunction of windows not closing , exterior wood siding and trim breakage etc... , can you please clarify who will be responsible to restore these items?

A1. Refer to note on "Procedure for column straightening" on S701. Note 2: "secure outer flange from horizontal movement with temporary shoring.." As noted in Drawing S-000, Division 1 General Requirements, Section A-4 regulations and conditions of contract.

The contractor shall be responsible for repairs or replacement at the contractor's expense of any damages caused to existing installation and systems as a result of their work.

This addendum forms part of the Request for Tender. In your Form of Tender, please indicate receipt thereof, failure to do so may result in the rejection of the tender submission.

For further information, please contact Julie-Ann Williams, Procurement Officer, Supply Services at Julie-Ann.Williams@ottawa.ca.

End of Addendum # 5